


CORNER NO.	MONUMENT	ACCESSORIES
①	FD. 2 1/2" ALUM. CAP IN 1" GI PIPE SET BY HAMBLETON.	FD. ORIGINAL BTS: 24" LARCH BEARS N21°E 25.0 FT.; 22" FIR BEARS S70°E 22.6 FT.; 25" LARCH BEARS N64°W 33.8 FT. SCRIBED BTS: 9" W. FIR BEARS S12°E 50.7 FT., SCRIBED T9S R35E S26 BT; 17" E. SPRUCE BEARS S20°W 37.6 FT., SCRIBED T9S R35E S27 BT.
②	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 8" D. FIR BEARS S1°E 58.8 FT., SCRIBED MS 228 BC2 BT; 11" D. FIR BEARS S45°W 33.1 FT., SCRIBED MS 228 BC2 BT.
③	FD. 2 1/2" IRON PIPE AT CORNER POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL BTS: 19" D. FIR BEARS N5°W 12.5 FT., 16" D. FIR BEARS S62°W 23.8 FT., SCRIBED BTS: 10" LARCH BEARS N2°W 72.8 FT., SCRIBED 1/4 S23 BT; 13" D. FIR BEARS S24°W 30.3 FT., SCRIBED 1/4 S 26 BT.
④	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL BTS: 24" D. FIR STUMP BEARS N78°W 25.1 FT.; 18" LARCH BEARS N47°E 9.5 FT. SCRIBED BTS: 11" D. FIR BEARS N35°E 12.5 FT., SCRIBED MS 228 BB1 BC1 BT; 13" D. FIR BEARS S5°W 35.3 FT., SCRIBED MS 228 BB1 BC1 BT.
⑤	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 8" E. SPRUCE BEARS N27°W 34.5 FT., SCRIBED X BT; 15" E. SPRUCE BEARS N39°E 31.8 FT., SCRIBED X BT.
⑥	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL BT: 33" LARCH STUMP BEARS N44°E 9.2 FT. SCRIBED BTS: 11" E. SPRUCE BEARS N46°E 42.7 FT., SCRIBED MS 228 BB NCB BT; 19" W. FIR BEARS N13°E 35.0 FT., SCRIBED MS 228 BB NCB BT.
⑦	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 5" LARCH BEARS S31°E 75.9 FT., SCRIBED MS 228 BB4 BT; 12" D. FIR BEARS S40°W 76.0 FT., SCRIBED MS 228 BB4 BT.
⑧	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL BT: 24" D. FIR STUMP BEARS S51 1/2°E 17.8 FT. SCRIBED BTS: 12" P. PINE BEARS S78°W 23.8 FT., SCRIBED MS 228 S3 BB3 BT; 12" D. FIR BEARS N4°W 40.5 FT., SCRIBED MS 228 S3 BB3 BT.
⑨	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 19" D. FIR BEARS S46°E 55.6 FT., SCRIBED X BT; 7" D. FIR BEARS WEST 40.3 FT., SCRIBED X BT.
⑩	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 12" D. FIR BEARS S58°W 22.6 FT., SCRIBED CW 1/16 S26 BT; 6" P. PINE BEARS N20°W 37.6 FT., SCRIBED CW 1/16 S26 BT.
⑪	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 9" W. FIR BEARS S1°W 10.1 FT., SCRIBED CEWW 1/256 S26 BT; 8" W. FIR BEARS S72°E 13.6 FT., SCRIBED CEWW 1/256 S26 BT.
⑫	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	SCRIBED BTS: 13" D. FIR BEARS S53°W 38.2 FT., SCRIBED C-E-NW-SW 1/256 S26 BT; 9" D. FIR BEARS S19°E 31.5 FT., SCRIBED C-E-NW-SW 1/256 S26 BT.

CORNER NO.	MONUMENT	ACCESSORIES
⑬	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL BTS: 24" PINE SNAG BEARS S11°W 47.5 FT.; 25" P. PINE BEARS N43°W 27.7 FT., SCRIBED BT: 17" D. FIR BEARS S20°W 12.4 FT., SCRIBED MS 228 S2 BT.
⑭	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL BT: 27" P. PINE BEARS S87°E 15.2 FT. SCRIBED BT: 9" D. FIR BEARS N 85°W 27.1 FT., SCRIBED MS 228 S SWCE BT.
⑮	FD. 1 1/2" GI PIPE AT CORNER POSITION. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL 12" P. PINE BT (NOW STUB) BEARS S34°E 23.8 FT. FD. 2" GI P. AT BASE OF STUB, (NO RECORD) MARKD. BT 12" PINE S34°E 361KS. SCRIBED BTS: 10" D. FIR BR S 73°E 8.3 FT., SCRIBED 1/4 S26 BT; 15" P. PINE BR S 79°W 31.7 FT., SCRIBED 1/4 S27 BT.
⑯	FD. REMAINS OF ORIGINAL SQUARED POST WITH SCRIBING. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL BTS: 31" PINE SNAG BEARS N61°E 19.8 FT.; 24" PINE STUMP BEARS S 10°W 29.0 FT. SCRIBED BTS: 9" W. FIR BEARS N20°E 8.4 FT., SCRIBED MS 228 LC-1 S5 BT; 8" W. FIR BEARS S56°E 6.0 FT., SCRIBED MS 228 LC-1 S-5 BT.
⑰	SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL BTS: 36" PINE STUMP BEARS S56°W 18.5 FT.; 42" PINE STUMP BEARS N72°W 27.1 FT. SCRIBED BTS: 6" W. FIR BEARS N1°E 20.6 FT., SCRIBED MS 228 LC SWCE BT; 9" W. FIR BEARS S77°W 22.0 FT., SCRIBED MS 228 LC SWCE BT.
⑱	FD. REMAINS OF OLD POST WITH SCRIBING. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL BTS: 17" W. FIR BEARS S14°W 15.8 FT.; ROTTED W. FIR WINDTHROW BEARS N13 1/2°E 13.9 FT. SCRIBED BTS: 6" W. FIR BEARS S35°E 17.1 FT., SCRIBED MS 228 LC4 BT; 8" D. FIR BEARS S40°W 48.8 FT., SCRIBED MS 228 LC4 BT.
⑲	FD. ROTTED REMAINS OF ORIGINAL POST. SET 2 1/2" BRASS CAP IN 2 1/2" X 30" GI PIPE - ROCK MOUND.	FD. ORIGINAL BT: 18" LARCH BEARS S77°W 16.0 FT. SCRIBED BTS: 6" W. FIR BEARS S50°E 15.4 FT., SCRIBED MS 228 LC3 BC3 BT; 10" W. FIR BEARS N13°E 12.3 FT., SCRIBED MC228 LC3 BC3 BT.

NOTE: ALL NEW BTS ARE FACED AND MARKED PER BLM MANUAL AND IN ADDITION HAVE A BRASS WASHER MARKED LS 1305 NAILED FLUSH IN LOWER BLAZE. ALL BTS ARE PAINTED WITH 6" RED BAND AND TAGGED WITH APPROPRIATE SIGNS. ALL CORNERS SET ARE STAMPED AS PER BLM MANUAL PLUS PLS 1305 AND 1982. SUBDIVISION, BUT NOT MINING CLAIM CORNERS, ARE ALSO STAMPED WITH THE TOWNSHIP AND RANGE. 6 FT STEEL POSTS WITH APPROPRIATE SIGNS WERE SET 3 TO 5 FT FROM ALL CORNERS SET AS PER CONTRACT. FIELD NOTES ARE IN BOOKS A, B, C, O AND Q CONTRACT NO. 53-0-9M3-2-2789.



RECEIVED AND FILED
FEB 23 1983

OFFICE OF COUNTY SURVEYOR
Robert D. Borch
Attest: Nancy Hamilton